



- SF- Silt Fence/Earth Berm etc.
- CE- Gravel Construction Entrance
- SUB- Sidewalk Subgrade Barrier
- IP- Inlet Protection
- BZ- Buffer Zone
- CW- Concrete Washout
- TR- Trash/ Waste Container
- PT- Portable Toilet

EROSION CONTROL NOTES:

1. AREAS DELINEATED ON THE PLAN AS A "BUFFER ZONE" SHALL BE CLEARLY MARKED IN THE FIELD WITH ORANGE CONSTRUCTION FENCING PRIOR TO THE START OF ANY GROUND DISTURBING ACTIVITIES.
2. A STABILIZED GRAVEL CONSTRUCTION ENTRANCE SHALL BE INSTALLED AS FIRST SITE ACTIVITY.
3. EROSION CONTROL MEASURES SHALL BE INSPECTED DAILY AND MAINTAINED AS NECESSARY TO ENSURE THEIR FUNCTION.
4. EROSION CONTROL MEASURES SHALL BE KEPT IN PLACE UNTIL PERMANENT GROUND COVER IS ESTABLISHED.

SINGLE FAMILY RESIDENCE
 TYPICAL EROSION PREVENTION AND SEDIMENT CONTROL PLAN

